SECTION 011100 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes the following:

1. Work covered by the Contract Documents.
2. Work phases.
3. Work under other contracts.
4. Government Furnished Materials.
5. Use of premises.
6. Government's occupancy requirements.

1.2 WORK COVERED BY CONTRACT DOCUMENTS

A. Project Location: Various parks in the Pacific West and Intermountain regions.

B. The Work consists of the following: Installation of gates and closure structures on mine access points. This will provide for the safety of park visitors and employees. Some gates and closure structures will also allow for the safe entrance to and the preservation of habitat for various animal species that occupy the mines, where appropriate.

Project will be constructed under multiple contracts.

1.3 USE OF PREMISES

A. General: Contractor shall have limited use of premises for construction operations as indicated on Drawings by the Contract limits.

B. Storage of Materials: Confine storage of materials to areas directed by the Contracting Officer.

C. Use of Site: Limit use of premises to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1. Limits: Confine constructions operations to locations as directed by Contracting Officer.

2. Protection of Fauna:
   a. Do not remove, injure, or disturb fauna inhabiting work areas. Consult with the Contracting Officer if fauna activity impedes work related to this project.

   b. Protocol for Prevention of the Spread of White-Nose Syndrome in Bats**:** As per NPS directive issued April 17, 2009, regarding the prevention of the spread of white-nose syndrome in bats, any member of the work crew who has done fieldwork at a cave or abandoned mine in the states of Connecticut, Massachusetts, New Hampshire, New Jersey, New York, Pennsylvania, Vermont, Virginia, West

Virginia, North Carolina, Tennessee, Kentucky, and Ohio **regardless of whether white-nose syndrome has been confirmed** needs to either bring new clothes, boots, gloves, and equipment (NPS preference) or follow the decontamination procedures in White Nose Syndrome in Bats Decontamination Protocol form when performing work in caves or abandoned mine lands in units of the National Park System. A White Nose Syndrome in Bats Decontamination Protocol form will be issued prior to or at the Pre-Construction conference and must be signed by all work crew performing work in the park. Each member of the work crew must provide a signed copy of the form to the Contracting Officer prior to beginning work in the park.

3. Preservation of Natural Features:

   a. Prevent damage to natural surroundings. Restore damaged areas, repairing or replacing damaged trees and plants, at no additional expense to the Government.
   b. Provide temporary barriers to protect existing trees and plants and root zones.
   c. Do not remove, injure, or destroy trees or other plants without prior approval. Consult with Contracting Officer and remove agreed-on roots and branches that interfere with construction. If Contracting Officer directs, the Contractor shall be required to salvage, maintain, and/or replant plants or transplant plants as required by the requirements of the project.
   d. Do not fasten ropes, cables, or guys to existing trees.
   e. Carefully supervise excavating, grading, filling, and other construction operations near trees to prevent damage.

4. Government Occupancy: Allow for Government occupancy of Project site.
5. Driveways and Entrances: Keep roadways and entrances serving premises clear and available to Government, Government's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.

   a. Schedule deliveries to minimize use of roadways and entrances.
   b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.

D. Construction Camp: Establishment of a camp will be permitted as directed by Contracting Officer. Provide utilities as specified in Division 1 Section “Temporary Facilities and Controls”. Keep camp neat and clean and return site to previous condition at completion of work. These requirements also apply to all Contractors’ employees who may, with prior approval, establish their own camping facilities.

E. Hauling Restrictions: Comply with all legal load restrictions in the hauling of materials. Load restrictions on park roads are identical to the state load restrictions with such additional regulations as may be imposed by the Park Superintendent. Information regarding rules and regulations for vehicular traffic on park roads may be obtained from the Office of the Park Superintendent or Maintenance Headquarters. A special permit will not relieve Contractor of liability for damage which may result from moving of equipment.

F. American Recovery and Reinvestment Act (ARRA) Visitor Information Sign Requirements: All ARRA projects must display a visitor information sign that meets the ARRA Visitor Information Sign Requirements attached to the end of this specification.

1. The sign must be fabricated and installed in a prominent location on site within 10 days after Notice to Proceed is issued for this project.
2. Maintain sign in like new condition throughout the contract period.
3. Remove the sign within 10 days after substantial completion of the project.

1.4 GOVERNMENT'S OCCUPANCY REQUIREMENTS

A. Full Government Occupancy: Government will occupy site during entire construction period. Cooperate with Government during construction operations to minimize conflicts and facilitate Government usage.

B. Public Use of Site
   1. Contractor shall at all times conduct his operations to ensure the least inconvenience to the public. Road closures will be permitted, when required, upon specific approval of Contracting Officer.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011100